



SPECIFICATION

DESIGN/INSTALLATION OF NEW PLAY EQUIPMENT ON DALELANDS PLAY AREA, MARKET DRAYTON, TF9 1DQ

Market Drayton Town Council (MDTC) is seeking tenders from competent contractors to:

- design and install new metal play equipment and protective ground surfacing.
- repair protective ground surfacing where necessary.
- repair and enhance the children's cycle/scooter path; this could include installation of suitable equipment, signage, tarmac safety marking etc.

Market Drayton Town council will expect the complete installation to be of a high standard.

The Play Area equipment should be inclusive and suitable for children 5 – 12 years of age with the exception of a small allocation, minimum two pieces of equipment for 0-5 years.

Design to include:

- two benches.
- sensory play equipment
- a minimum of two pieces of equipment suitable for disabled children
- five aside goalposts complete with ball stop net and post system
- a basketball net
- repair and enhance the children's cycle/scooter path; this could include installation of suitable equipment, signage, tarmac safety marking etc.
- to remove the metal ramp on the cycle path

The zip wire to remain in place along with the safety fence.

All other existing fencing on the play area which may impede the design can be removed if required.

All old play equipment, fencing and ground materials to be removed from site by the contractor.

Play Equipment must be in accordance with BS EN 1176.

All equipment must be installed with suitable surfacing that meets BS EN 1177.

Technical specifications and pictures or drawings of all new equipment plus two layout plans (maximum size A2) must be supplied along with the tender documents.

Details of work to be undertaken on existing equipment to be listed.

To reinstate and make good all the surfaces and surrounding area.

Correct signage to the appropriate standard to be installed

A RAMS to be submitted before commencement of any work to cover the period of works.

The contractor will be responsible for all Health and Safety Responsibility for the duration of the works for employees and sub-contractors.

The contractor will be responsible for organising a ROPSA inspection on completion before acceptance by the Council (The zip wire will be excluded from the Inspection)

Final completion certificate to be provided.